

AFRL-SR-BL-TR-99-

REPORT DOCUMENTATION PAGE

Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing the data needed, and completing and reviewing this collection of information. Send comments regarding this burden estimate reducing this burden to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503

8/20

 Maintaining
 ns for
 Office of

1. AGENCY USE ONLY (Leave blank)		2. REPORT DATE April 29, 1999		3. REPORT TYPE AND DATES COVERED Final Technical Report (2/1/98 - 1/31/99)	
4. TITLE AND SUBTITLE Friction, Adhesion and Lubrication of Nanoscale Mechanical Systems.				5. FUNDING NUMBERS AFOSR # 49620-98-1-0237	
6. AUTHOR(S) Jacqueline Krim, P.I.					
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) North Carolina State University, Box 7514 Raleigh, NC 27695-7514				8. PERFORMING ORGANIZATION REPORT NUMBER	
9. SPONSORING / MONITORING AGENCY NAME(S) AND ADDRESS(ES) Brian Sanders, Program Manager Air Force Office of Scientific Research AFOSR/NM 801 North Randolph St., Room 732 Arlington, VA 22203				10. SPONSORING / MONITORING AGENCY REPORT NUMBER	
11. SUPPLEMENTARY NOTES					
12a. DISTRIBUTION / AVAILABILITY STATEMENT DISTRIBUTION STATEMENT A Approved for Public Release Distribution Unlimited					12b. DISTRIBUTION CODE
13. ABSTRACT (Maximum 200 Words) The equipment purchased by this grant consisted of a variable temperature, ultra-high vacuum compatible scanning tunneling microscope. During the 12 month period in which the grant was in effect, we designed and assembled an ultra-high vacuum chamber to house the microscope, and added this chamber to an existing system. The construction period now complete, and a series of measurements have commenced. These include measurements of the uptake rate of the lubricant TBPP on Fe as a function of temperature, and a series of measurements of the nanomechanical properties of a number of potential lubricants for Micro-Electro-Mechanical Systems (MEMS) applications by means of a combined quartz microbalance/scanning tunneling microscopy technique.					
14. SUBJECT TERMS					15. NUMBER OF PAGES: 5, including cover page
					16. PRICE CODE
17. SECURITY CLASSIFICATION OF REPORT	18. SECURITY CLASSIFICATION OF THIS PAGE	19. SECURITY CLASSIFICATION OF ABSTRACT	20. LIMITATION OF ABSTRACT		

(1) Final Technical Report:

**FRICITION, ADHESION AND LUBRICATION OF NANOSCALE
MECHANICAL SYSTEMS.**

AFOSR grant # F49620-98-1-0237 Reporting Period: 01 Feb. 1998 – 31 Jan. 1999

PI: Jacqueline Krim, North Carolina State University

**PI Address: Physics Department, Box 8202, North Carolina State University,
Raleigh, NC 27695-8202**

19990517 014


DTIC QUALITY INSPECTED 4

The instrumentation purchased by this grant was intended to enhance the capabilities of an existing apparatus devoted to research on nanotribology. The enhancements allowed molecular-scale studies of friction, adhesion and lubrication to be performed on materials of relevance to MEMS and smaller mechanical systems. In particular, the new capabilities allow friction force microscopy studies of the mechanical and chemical nature of the contact zone of a micromechanical contact, adhesive forces of metal-metal contact regions, and the exploration of the viability of vapor-phase lubricants for performance optimization in nanomechanical systems.

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES
TOLERANCES
DECIMALS ANGULAR
X.XX \pm 0.005 \pm 0.1
X.X \pm 0.003 \pm 0.1
30 HRT SCALE DRAWING

nan chamber
gate valve
frame 1
STM chamber
frame 2
air leg
adjustable foot

UHV 300 STM SYSTEM		
NCSU System : Frame		
SIZE	DESIGN and DRAWN	REV
A	Zhouhang Wang	1.0
SCALE	DWG NO.	REVISION
1:10	UHV300-NCSU-01	N/A
DATE	12/09/98	INK P/N : X/A



 RHK
 TECHNOLOGY

Copyright © 1994 - 1998, RHK Technology Inc. All Rights Reserved

Figure 1: Schematic of the new additions to the existing chamber. The STM addition is now in place and the entire system has been mounted on vibration isolation legs.

Figure 2 depicts a typical image recorded with the new microscope: Atomic gold step edges are easily visible.




Figure 2: Atomic Step edges of gold imaged with the new scanning tunneling microscope.

The apparatus is now entirely dedicated to our research supported by AFOSR grant # F49620-98-1-02-1, *Vapor-phase Lubricants: Nanometer-scale Mechanisms and Applications to Sub-micron and Rotating Machinery*.

We are currently measuring uptake rates of the lubricant TBPP on metal surfaces at various temperatures. Our studies of combined STM/QCM have demonstrated that a single asperity contact can be made in sliding contact at realistic sliding speeds. Our newest finding is that the tip can be employed for sliding with billions of passes, and then used to image the sliding contact region in areas as small as tens of atoms in lengthscale. This has immediate application to improving the tribological performance of MEMS systems. Moreover, this approach has proven to be far superior to that of an AFM/surface contact. The STM image depicted below was recorded on a silver film which deposited on the surface of a QCM and then exposed to oxygen. The brighter region of the image

corresponds to an area in which the oxygen overlayer was rubbed off, and then the damaged area reimaged. Figure 3 was recorded on an existing STM in our lab with very limited capabilities: In the upcoming year, we plan to implement the joint QCM/STM capabilities to the RHK microscope.




Figure 3: STM image of a silver film which has been in rubbing contact for 10 billion passes with a quartz crystal oscillator.